

TEST REPORT

Report No.: C6391.01-301-44

Rendered to:

International Window Fullerton, California

PRODUCT TYPE: Polyvinyl Chloride (PVC) XOX Horizontal Sliding Window **SERIES/MODEL**: 5420

SPECIFICATIONS: AAMA/WDMA/CSA 101/I.S.2/A440-05, Standard/Specification for Windows, Doors, and Unit Skylights.

| CAWM 301-90, Forced Entry Resistance Test for Windows | |
|---|--|
|---|--|

| Title | Summary of Results |
|--|---|
| Primary Product Designator | HS-LC25 3030 x 1811* (119 x 71*) |
| Design Pressure | ±1200 Pa (±25.06 psf) |
| Air Infiltration | 1.12 L/s/m ² (0.22 cfm/ft ²) |
| Water Penetration Resistance Test Pressure | 220 Pa (5.43 psf) |

Test Completion Date: 03/20/2013

Reference must be made to Report No. C6391.01-301-44 dated 04/04/13 for complete test specimen description and detailed test results. Reference Architectural Testing, Inc. Report No. C2278.01-301-44, dated 03/24/13 for complete *Gateway* test specimen description and test results.



| 1.0 Report Issued To: | International Window 1551 E. Orangethrope Ave. Fullerton, California 92831 |
|-----------------------|--|
| 2.0 Test Laboratory: | Architectural Testing, Inc. 2524 East Jensen Avenue Fresno, California 93706 (559) 233 - 8705 |

3.0 Project Summary:

- **3.1 Product Type**: Polyvinyl Chloride (PVC) XOX Horizontal Sliding Window
- 3.2 Series/Model: 5420
- **3.3 Compliance Statement**: Results obtained are tested values and were secured by using the designated test method(s). The specimen tested successfully met the performance requirements for a **HS-LC25 3030 x 1811* (119 x 71*)** rating. Reference Architectural Testing, Inc. Report No. C2278.01-301-44, dated 03/24/13 for complete *Gateway* test specimen description and test results.

General Note: An asterisk (*) next to the size designation indicates that the size tested for optional performance was smaller than the Gateway test size for the product type and class.

- **3.4 Test Dates:** 02/21/2013 03/20/2013
- **3.5 Test Record Retention End Date**: All test records for this report will be retained until March 24, 2017.
- 3.6 Test Location: Architectural Testing, Inc. test facility in Fresno, California.
- **3.7 Test Sample Source**: The test specimen was provided by the client. Representative samples of the test specimen will be retained by Architectural Testing for a minimum of four years from the test completion date.
- **3.8 Drawing Reference**: The test specimen drawings have been reviewed by Architectural Testing and are representative of the test specimen reported herein. Test specimen construction was verified by Architectural Testing per the drawings located in Appendix B. Any deviations are documented herein or on the drawings.

3.9 List of Official Observers:

<u>Name</u>

<u>Company</u>

| Jay Ratliff | Architectural Testing, Inc. |
|----------------|-----------------------------|
| David Douglass | Architectural Testing, Inc. |
| Jeffrey Osugi | Architectural Testing, Inc. |

www.archtest.com



4.0 Test Specifications:

AAMA/WDMA/CSA 101/I.S.2/A440-05, Standard/Specification for Windows, Doors, and Unit Skylights.

CAWM 301-90, Forced Entry Resistance Test for Windows.

5.0 Test Specimen Description:

5.1 Product Sizes:

| Overall Area: | Width | | Не | ight |
|--|-------------|----------|-------------|---------|
| 5.49 m ² (59.06 ft ²) | millimeters | inches | millimeters | inches |
| Overall size | 3030 | 119-1/4 | 1811 | 71-5/16 |
| Interior panel x 2 | 754 | 29-11/16 | 1754 | 69-1/16 |
| Screen x 2 | 719 | 28-5/16 | 1765 | 69-1/2 |

5.2 Frame Construction:

| Frame Member | Material | Description |
|---------------------------|----------|---|
| Head, sill and jambs | PVC | |
| Exterior meeting stile | PVC | |
| Roller track | PVC | Snap fit to sill and held back 1/4" from each end. |
| Siteline adapter | PVC | Snap fit to head and sill at fixed lite. Secured to the frame with $#6 \ge 1/2$ " Phillips pan head screws 2" from each end and mid-span. |

| | Joinery Type | Detail |
|---------------------------|--------------|--|
| Head, sill and jambs | Mitered | Fully welded. |
| Exterior meeting stile | Coped | Secured through the frame with two #8 x 2-1/2" Phillips flat head screws. The screws were sealed. |



5.0 Test Specimen Description: (Continued)

5.3 Panel Construction:

| Panel Member | Material | Description |
|-----------------------|----------|--|
| Top rail, bottom rail | PVC | The interlock was held back 1" from each end |
| and each stile | FVL | and 2-1/4" for the lock. |

| | Joinery Type | Detail |
|-------------|--------------|---------------|
| All corners | Mitered | Fully welded. |

5.4 Weatherstripping:

| Description | Quantity | Location |
|--------------------------------------|----------|-------------------------|
| 0.310" high polypile with center fin | 1 Row | All members of panel. |
| 0.450" high polypile with center fin | 1 Row | Exterior meeting stile. |

5.5 Glazing: No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.

| Glass Type | Spacer Type | Interior Lite | Exterior Lite | Glazing Method | |
|---------------|--------------------------|------------------|------------------|---|--|
| 3/4" I(| U shaped coated steel | 1/8" Annealed | 1/8" Annealed | Exterior glazed onto a 3/8" wide x 1/16" high glazing tape and secured with a snap in PVC glazing bead. | |

| Location | Quantity | Daylig | Glass Bite | |
|-------------------------|-------------------|-------------|------------------|------------|
| Location | Location Quantity | | inches | Glass bite |
| Fixed lite | 1 | 1430 x 1663 | 56-5/16 x 65-1/2 | 3/8" |
| Left interior panel | 1 | 673 x 1673 | 26-1/2 x 65-7/8 | 5/16" |
| Right interior panel | 1 | 672 x 1674 | 26-7/16 x 65-7/8 | 5/16" |



5.0 Test Specimen Description: (Continued)

5.6 Drainage:

| Drainage Method | Size | Quantity | Location |
|------------------------|---|----------|---|
| Weephole with cover | 1-3/4" x 1/4" (1-1/4" x 1/8" effective) | 6 | 3-5/8", 23-3/8" and 33-3/4" from each end through exterior sill face. |
| Weephole | 1/4" round | 8 | 2-1/8" from each end through screen track. 1" from each end through sill siteline adapter. 1-1/4" from each end through bottom rail of interior panels. |
| Weephole | 1/2" round | 6 | 4-3/4", 24-3/4" and 34-1/4" from each end through sill track through internal webbing. |
| Weephole | 1/8" round | 4 | 1/4" from each side of exterior meeting stiles through screen track. |

5.7 Hardware:

| Description | Quantity | Location |
|-----------------------------|----------|--|
| Auto lock | 2 | Midspan on interior meeting stile. The faceplate was secured to the lock with two $\#6 \ge 1/2$ " Phillips flat head screws. |
| Keeper | 2 | Opposite lock on exterior meeting stile secured with two #8 x 1" Phillips flat head self-drilling screws into reinforcement. |
| Plastic roller with housing | 4 | 3-1/4" from each end on bottom rail. |
| Secondary lock | 2 | Bottom of interior meeting stile secured with two 8-32 x 5/8" Phillips pan head screws into reinforcement. |
| Secondary lock keeper | | 31-1/4" from lock jamb secured through roller track and sill with two #6 x 1/2" Phillips pan head screws. |



5.0 Test Specimen Description: (Continued)

5.8 Reinforcement:

| Drawing Number | Location | Material |
|----------------|---|-------------------|
| 50600 | Exterior meeting stile | Extruded aluminum |
| 50601 | Interior meeting stile | Extruded aluminum |
| 50596 | 8" long at sill of frame at exterior meeting stile | Extruded aluminum |

5.9 Screen Construction:

| Frame Material | Corner Construction | Mesh Type | Mesh Attachment Method | |
|----------------|----------------------------|------------|------------------------|--|
| Roll formed | Square cut with | Fiborglass | Hollow spline | |
| aluminum | corner key | Fiberglass | | |

6.0 Installation:

The specimen was installed into a Spruce-Pine-Fir wood buck. The rough opening allowed for a 1/8 - 3/16" shim space. The exterior perimeter of the window was sealed with silicone. The frame perimeter was blocked with 2 x 2 wood.

| Location | Anchor Description | Anchor Location |
|----------------------|--------------------|---|
| Head, sill and jambs | 3" drywall screws | 4" from each and 16" on center through the 2 x 2 wood and mounting fin. |



7.0 Test Results: The temperature during testing was 22 - 24°C (72 - 76°F). The results are tabulated as follows:

| Title of Test | Results | Allowed | Note |
|---------------------------------|-----------------------------|---------------------------------|---------|
| | Initiate motion: | | |
| | 66 N (14.8 lbf) | Report Only. | |
| Operating Force, | Maintain motion: | | |
| per ASTM E 2068 | 53 N (12.0 lbf) | 115 N (25.9 lbf) max. | |
| | Locks: | | |
| | 19 N (4.3 lbf) | 100 N (22.5 lbf) max. | |
| Air Leakage, | | | |
| Infiltration per ASTM E 283 | 1.12 L/s/m ² | 1.5 L/s/m ² | |
| at 75 Pa (1.57 psf) | (0.22 cfm/ft ²) | (0.3 cfm/ft ²) max. | 1 |
| Water Penetration, | | | |
| per ASTM E 547 | N/A | N/A | 3 |
| Uniform Load Deflection, | | | |
| per ASTM E 330 | | | |
| taken at exterior meeting stile | | | |
| +1200 Pa (+25.06 psf) | 14.5 mm (0.57") | | |
| -1200 Pa (-25.06 psf) | 12.8 mm (0.50") | Report Only. | 4, 5, 6 |
| Uniform Load Structural, | | | |
| per ASTM E 330 | | | |
| taken at exterior meeting stile | | | |
| +1800 Pa (+37.59 psf) | 0.0 mm (0.00") | | |
| -1800 Pa (-37.59 psf) | 0.5 mm (0.02") | 7.1 mm (0.28") max. | 5, 6 |
| Forced Entry Resistance, | | | |
| per ASTM F 588, | _ | | |
| Type: A - Grade: 10 | Pass | No entry | |
| Forced Entry Resistance, | | | |
| per CAWM 301, | _ | | |
| Туре: І | Pass | No entry | |



7.0 Test Results: (Continued)

| Title of Test | Results | Allowed | Note | |
|---------------------------|---------|-----------------|------|--|
| Thermoplastic Corner Weld | Pass | Meets as stated | | |
| Deglazing, | | | | |
| per ASTM E 987 | | | | |
| Operating direction, | | | | |
| 320 N (71.9 lbf) | Pass | Meets as stated | | |
| Remaining direction, | | | | |
| 230 N (51.7 lbf) | Pass | Meets as stated | | |
| Optional Performance | | | | |
| Water Penetration, | | | | |
| per ASTM E 547 | | | | |
| at 220 Pa (5.43 psf) | Pass | No leakage | 2 | |

Note 1: The tested specimen meets (or exceeds) the performance levels specified in AAMA/WDMA/CSA 101/I.S.2/A440 for air leakage resistance.

Note 2: With and without insect screen.

Note 3: The client opted to start at a pressure higher than the minimum required. Test results are reported under Optional Performance.

Note 4: The deflections reported are not limited by AAMA/WDMA/CSA 101/I.S.2/A440 for this product designation. The deflection data is recorded in this report for special code compliance and information only.

Note 5: Loads were held for 10 seconds.

Note 6: Tape and film were used to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.



Architectural Testing will service this report for the entire test record retention period. Test records that are retained such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by Architectural Testing, Inc. for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Architectural Testing, Inc.

For ARCHITECTURAL TESTING, Inc.

David Douglass Project Manager Leaton Kirk Director – Regional Operations

JO: ms

Attachments (pages): This report is complete only when all attachments listed are included.Appendix-A: Alteration Addendum (1)Appendix-B: Drawings (14) Complete drawings packet on file with Architectural Testing, Inc.

This report produced from controlled document template ATI 00438, issued 01/31/12.



Test Report No.: C6391.01-301-44 Report Date: 04/04/13 Record Retention End Date: 03/24/17

Appendix A

Alteration Addendum

Note: No alterations were required.



Appendix **B**

Drawings

Note: Complete drawings packet on file with Architectural Testing, Inc.